
### Illinois Tollway Base Sheet Revisions

Drawing	Drawings Modification Summary Effective: 03-31-2016
All	The electronic (pdf) version of the Standard Drawing are now made searchable (text).
	Erosion Sediment Control (ESC)-Series 200
	Sediment Basin Dewatering Device
	Revised Note 7, removed proprietary name from skimmer device.
	Roadway (RDY)-Series 400
M-RDY-408	Approach Slab, Mainline
	Changed Transverse Reinforcement size and spacing in the bottom mat of the bridge approach slab and transition apshoulder slabs from #6@9" to #8@4" to be in conformance with IDOT ABD Memo 15.8.
	Changed Transverse Reinforcement size and spacing in the top mat of the bridge approach slab and transition approach slabs from #5@12" to #5@6" to be in conformance with IDOT ABD Memo 15.8.
	Changed Longitudinal Reinforcement size and spacing in the top mat of the bridge approach slab and transition appr shoulder slabs from #4@15" to #5@6" to be in conformance with IDOT ABD Memo 15.8.
	Added note *** to clarify that base sheet reinforcement is for approach slabs not located on retaining walls. If approach splaced on retaining wall, reinforcement shall be designed for TL-5 crash loading.
	Changed spacing and shape of both dxx vertical bars in the barrier on the bridge approach slab and transition approashoulder slab to match the vertical bars in the bridge parapet and moment slab barrier.
All	Changed top mat reinforcement cover to 2.25" to be consistent with deck and moment slab clearances.
Sheets 1,2	Updated Note to Designer for Drainage Structures. Designer to determine size, type and location.
Sheets 1,2	Changed approach slab shoulder width requirements to match Structures Design Manual.
Sheet 3	Added option of using subgrade aggregate, special under the transition approach slab.
Sheet 3	Added additional Approach Slab Barrier Elevation to distinguish between non-integral and integral/semi-integral abutr
	Eliminated Optional Longitudinal Joint Within a Traffic Lane detail.
	Changed Neoprene Sheet to Elastomeric Sheet to keep call out generic and not specific.
	Revised Bill of Material to clarify Pay Items and Pay Item Numbers to be included.  Added note to Typical Barrier Transition Detail to clarify where the 1'-9" dimension should be measured.
M-RDY-409	Approach Slab, Ramp
	Changed Transverse Reinforcement size and spacing in the bottom mat of the bridge approach slab and transition ap shoulder slabs from #6@9" to #8@4" to be in conformance with IDOT ABD Memo 15.8.
All	Changed Transverse Reinforcement size and spacing in the top mat of the bridge approach slab and transition appro shoulder slabs from #5@12" to #5@6" to be in conformance with IDOT ABD Memo 15.8.
All	Changed Longitudinal Reinforcement size and spacing in the top mat of the bridge approach slab and transition approach slabs from #4@15" to #5@6" to be in conformance with IDOT ABD Memo 15.8.
	Added note *** to clarify that base sheet reinforcement is for approach slabs not located on retaining walls. If approach is placed on retaining wall, reinforcement shall be designed for TL-5 crash loading.
All	Changed spacing and shape of both dxx vertical bars in the barrier on the bridge approach slab and transition approa shoulder slab to match the vertical bars in the bridge parapet and moment slab barrier.
	Changed top mat reinforcement cover to 2.25" to be consistent with deck and moment slab clearances.
	Updated Note to Designer for Drainage Structures. Designer to determine size, type and location.  Changed approach slab shoulder width requirements to match Structures Design Manual.
	Added option of using subgrade aggregate, special under the transition approach slab.
	Added additional Approach Slab Barrier Elevation to distinguish between non-integral and integral/semi-integral abutr
	Eliminated Optional Longitudinal Joint Within a Traffic Lane detail.
	Changed Neoprene Sheet to Elastomeric Sheet to keep call out generic and not specific.
Sheet 5	Revised Bill of Material to clarify Pay Items and Pay Item Numbers to be included.
Sheet 5	Added note to Typical Barrier Transition Detail to clarify where the 1'-9" dimension should be measured.
M-RDY-410	Reserved
	Emergency Turnaround Median Width <u>&gt;</u> 35 Ft
	Bridge (BRG)-Series 500
	Expansion Joint Repair Base Sheet was removed since details did not match Special Provision.
	Crash Wall Modifications Median Piers
M-BRG-507	Crash Wall Modifications Median Piers  Note 4 - Changed Reinforcing bars to Reinforcement Bars.
M-BRG-507 M-BRG-508	
M-BRG-507 M-BRG-508	Note 4 - Changed Reinforcing bars to Reinforcement Bars.  Crash Wall Modifications Shoulder Piers  Note 4 - Changed Reinforcing bars to Reinforcement Bars.
M-BRG-507 M-BRG-508	Note 4 - Changed Reinforcing bars to Reinforcement Bars.  Crash Wall Modifications Shoulder Piers  Note 4 - Changed Reinforcing bars to Reinforcement Bars.  Slopewall Details
M-BRG-507 M-BRG-508 M-BRG-525	Note 4 - Changed Reinforcing bars to Reinforcement Bars.  Crash Wall Modifications Shoulder Piers  Note 4 - Changed Reinforcing bars to Reinforcement Bars.  Slopewall Details  Drainage (DRN)-Series 600
M-BRG-508 M-BRG-525 M-DRN-601	Note 4 - Changed Reinforcing bars to Reinforcement Bars.  Crash Wall Modifications Shoulder Piers  Note 4 - Changed Reinforcing bars to Reinforcement Bars.  Slopewall Details  Drainage (DRN)-Series 600  Slope Drain
M-BRG-508 M-BRG-525 M-DRN-601	Note 4 - Changed Reinforcing bars to Reinforcement Bars.  Crash Wall Modifications Shoulder Piers  Note 4 - Changed Reinforcing bars to Reinforcement Bars.  Slopewall Details  Drainage (DRN)-Series 600
M-BRG-508 M-BRG-525 M-DRN-601	Note 4 - Changed Reinforcing bars to Reinforcement Bars.  Crash Wall Modifications Shoulder Piers  Note 4 - Changed Reinforcing bars to Reinforcement Bars.  Slopewall Details  Drainage (DRN)-Series 600  Slope Drain  Revised storm sewer to "Class B, 12".

<b>Base Sheet</b>	Drawings
Drawing	Modification Summary   Effective: 03-31-2016
	Maintenance of Traffic (MOT)-Series 700
M-MOT-700	Temporary Concrete Barrier "Y" Connector Segment
	Revised Barrier Details Notes.  Changed barrier edges chamfered from 1/2" to 1" on all edges (optional).
	Onangea samer eages anamierea nom 1/2 to 1 on an eages (optional).
	Overhead Sign (OHS)-Series 720
M-OHS-720	Overhead Sign Structure Span Type Summary and Total Bill of Material
	Added Protective Coat (SQ YD) to Summary Table
	Clarified Class SI and Class DS Concrete are included in Foundation For Overhead Sign Structure.
M-OHS-721	Overhead Sign Structure Cantilever Type Summary and Total Bill of Material
0110 121	Added Protective Coat (SQ YD) to Summary Table
	Clarified Class SI and Class DS Concrete are included in Foundation For Overhead Sign Structure.
M-OHS-722	Overhead Sign Structure Entrance Monotube Type (Steel) Mainline Summary and Total Bill of Materia
	Added Protective Coat (SQ YD) to Summary Table
	Clarified Class SI and Class DS Concrete are included in Foundation For Overhead Sign Structure.  Clarified Concrete Structures is for Single Face Barrier and included in Summary Table and Total Bill of Mate
	Claimed Concrete Structures is for Single race partier and included in Summary rable and rotal bill of Mate
M-OHS-723	Overhead Sign Structure Exit Monotube Type (Steel) Mainline Summary and Total Bill of Material
	Added Protective Coat (SQ YD) to Summary Table
	Clarified Class SI and Class DS Concrete are included in Foundation For Overhead Sign Structure.
	Clarified Concrete Structures is for Single Face Barrier and included in Summary Table and Total Bill of Mate
M 0110 ==	Overhead Cinn Chrystone Dutterfly Time (Otto I) Comments   T.   Dill. (15)
M-OHS-724	Overhead Sign Structure Butterfly Type (Steel) Summary and Total Bill of Material
	Added Protective Coat (SQ YD) to Summary Table Clarified Class SI and Class DS Concrete are included in Foundation For Overhead Sign Structure.
	Removed Truss Extension for Mounting Walkway detail and references
	Added "L" column and removed TGL and TGL1 from the Summary Table
	The state of the s
M-OHS-725	Overhead Sign Structure Entrance Monotube Type (Steel) AET Ramp Summary and Total Bill of Mate
	Added Protective Coat (SQ YD) to Summary Table
	Clarified Class SI and Class DS Concrete are included in Foundation For Overhead Sign Structure.
	Clarified Concrete Structures is for Single Face Barrier and included in Summary Table.
M 0110 700	Overland Circ Circ Circ Circ Edit Manager Language Circ NAFT Barrer Commence Language Language Circ National Circ Circ Circ Circ Circ Circ Circ Circ
M-OHS-726	Overhead Sign Structure Exit Monotube Type (Steel) AET Ramp Summary and Total Bill of Material  Added Protective Coat (SQ YD) to Summary Table
	Clarified Class SI and Class DS Concrete are included in Foundation For Overhead Sign Structure.
	Clarified Concrete Structures is for Single Face Barrier and included in Summary Table.
	Olarined Controlle Christians is for Chigie Face Barrier and included in Curimary Fable.
M-OHS-727	Overhead Sign Structure Exit Monotube Type (Steel) Cash-IPO Ramp Summary and Total Bill of Mate
	Added Protective Coat (SQ YD) to Summary Table
	Clarified Class SI and Class DS Concrete are included in Foundation For Overhead Sign Structure.
	Clarified Concrete Structures is for Single Face Barrier and included in Summary Table.
M OUE 700	Overhand Cinn Chrystoria Chan Time (Charl) Comment and Total Bill of Material
IVI-UF13-728	Overhead Sign Structure Span Type (Steel) Summary and Total Bill of Material  Added Protective Coat (SQ YD) to Summary Table
	Clarified Class SI and Class DS Concrete are included in Foundation For Overhead Sign Structure.
	Starting Stage Starta Stage 25 Controlled are included in 1 canadator 1 of Storthoad Sign Structure.
M-OHS-729	Overhead Sign Structure ITS Gantry Frame (Steel) Single Span Structure Details
Sheet 1	Revised Material Specification Table to specify ASTM A500 Gr C & B for Frame & Mounting Beam HSS, respectively.
Sheet 4	Removed Note 6, referring to ASTM requirements of HSS members.
Sheet 5	Revised Note 1 to clarify requirements for Contractor when soil conditions are not met in the field.
Sheet 5	Removed Protective Coat quantity since not required to be applied to shoulder foundation.
Sheet 5	Updated anchor bolt note to allow ASTM F1554 bolts.
Sheet 6 Sheet 6	Revised Note 1 to clarify requirements for Contractor when soil conditions are not met in the field.  Removed Protective Coat quantity since not required to be applied to shoulder foundation.
Sheet 6	Added note 5 to clarify limits of protective coat and revised protective coat quantity in Median Foundation Schedule.
OHOGE I	nassa noto o to otaniy ininto of protoctive coat and revised protective coat quantity in inedian Foundation ochedule.
M-OHS-730	Overhead Sign Structure ITS Gantry Frame (Steel) Two-Span Structure Details
Sheet 1	Revised Material Specification Table to specify ASTM A500 Gr C & B for Frame & Mounting Beam HSS, respectively.
Sheet 4	Removed Note 6, referring to ASTM requirements of HSS members.
Sheet 6	Revised Note 1 to clarify requirements for Contractor when soil conditions are not met in the field.
Sheet 6	Removed Protective Coat quantity since not required to be applied to shoulder foundation.
	Updated anchor bolt note to allow ASTM F1554 bolts.  Revised Note 1 to clarify requirements for Contractor when soil conditions are not met in the field.
Sheet 6	IKE VISED INOTE 1 TO CIARTLY REQUIREMENTS FOR CONTRACTOR When SOIL CONDITIONS ARE NOT MET IN THE FIELD
Sheet 7	
Sheet 7 Sheet 7	Removed Protective Coat quantity since not required to be applied to shoulder foundation.
Sheet 7	
Sheet 7 Sheet 7	Removed Protective Coat quantity since not required to be applied to shoulder foundation.  Added note 5 to clarify limits of protective coat and revised protective coat quantity in Median Foundation Schedule.
Sheet 7 Sheet 7 Sheet 8	Removed Protective Coat quantity since not required to be applied to shoulder foundation.
Sheet 7 Sheet 7 Sheet 8 M-ITS-1000	Removed Protective Coat quantity since not required to be applied to shoulder foundation.  Added note 5 to clarify limits of protective coat and revised protective coat quantity in Median Foundation Schedule.  Pole Assembly-Series 1000  ELEVATION VIEWS POLE MOUNTED ITS ELEMENT ASSEMBLY  Added 30A-2P NEMA 4X DISC MTD ON SUPPORT DETAIL.
Sheet 7 Sheet 7 Sheet 8 M-ITS-1000	Removed Protective Coat quantity since not required to be applied to shoulder foundation.  Added note 5 to clarify limits of protective coat and revised protective coat quantity in Median Foundation Schedule.  Pole Assembly-Series 1000  ELEVATION VIEWS POLE MOUNTED ITS ELEMENT ASSEMBLY  Added 30A-2P NEMA 4X DISC MTD ON SUPPORT DETAIL.  GENERAL NOTES POLE MOUNTED ITS ELEMENT ASSEMBLY
Sheet 7 Sheet 7 Sheet 8 M-ITS-1000 M-ITS-1001	Removed Protective Coat quantity since not required to be applied to shoulder foundation.  Added note 5 to clarify limits of protective coat and revised protective coat quantity in Median Foundation Schedule.  Pole Assembly-Series 1000  ELEVATION VIEWS POLE MOUNTED ITS ELEMENT ASSEMBLY  Added 30A-2P NEMA 4X DISC MTD ON SUPPORT DETAIL.  GENERAL NOTES POLE MOUNTED ITS ELEMENT ASSEMBLY  Added Note 16 regarding disconnect switch usage.
Sheet 7 Sheet 7 Sheet 8 M-ITS-1000 M-ITS-1001	Removed Protective Coat quantity since not required to be applied to shoulder foundation.  Added note 5 to clarify limits of protective coat and revised protective coat quantity in Median Foundation Schedule.  Pole Assembly-Series 1000  ELEVATION VIEWS POLE MOUNTED ITS ELEMENT ASSEMBLY  Added 30A-2P NEMA 4X DISC MTD ON SUPPORT DETAIL.  GENERAL NOTES POLE MOUNTED ITS ELEMENT ASSEMBLY  Added Note 16 regarding disconnect switch usage.  ITS STANDARD FOUNDATION: New Sheet
Sheet 7 Sheet 7 Sheet 8  M-ITS-1000  M-ITS-1001	Removed Protective Coat quantity since not required to be applied to shoulder foundation.  Added note 5 to clarify limits of protective coat and revised protective coat quantity in Median Foundation Schedule.  Pole Assembly-Series 1000  ELEVATION VIEWS POLE MOUNTED ITS ELEMENT ASSEMBLY  Added 30A-2P NEMA 4X DISC MTD ON SUPPORT DETAIL.  GENERAL NOTES POLE MOUNTED ITS ELEMENT ASSEMBLY  Added Note 16 regarding disconnect switch usage.  ITS STANDARD FOUNDATION: New Sheet  Dynamic Message Sign (ITS) - Series 1100
Sheet 7 Sheet 7 Sheet 8  M-ITS-1000  M-ITS-1001  M-ITS-11002	Removed Protective Coat quantity since not required to be applied to shoulder foundation.  Added note 5 to clarify limits of protective coat and revised protective coat quantity in Median Foundation Schedule.  Pole Assembly-Series 1000  ELEVATION VIEWS POLE MOUNTED ITS ELEMENT ASSEMBLY  Added 30A-2P NEMA 4X DISC MTD ON SUPPORT DETAIL.  GENERAL NOTES POLE MOUNTED ITS ELEMENT ASSEMBLY  Added Note 16 regarding disconnect switch usage.  ITS STANDARD FOUNDATION: New Sheet  Dynamic Message Sign (ITS) - Series 1100  Revised conduit call-outs
Sheet 7 Sheet 7 Sheet 8  M-ITS-1000  M-ITS-1001  M-ITS-1100  M-ITS-1100  M-ITS-1100	Removed Protective Coat quantity since not required to be applied to shoulder foundation.  Added note 5 to clarify limits of protective coat and revised protective coat quantity in Median Foundation Schedule.  Pole Assembly-Series 1000  ELEVATION VIEWS POLE MOUNTED ITS ELEMENT ASSEMBLY  Added 30A-2P NEMA 4X DISC MTD ON SUPPORT DETAIL.  GENERAL NOTES POLE MOUNTED ITS ELEMENT ASSEMBLY  Added Note 16 regarding disconnect switch usage.  ITS STANDARD FOUNDATION: New Sheet  Dynamic Message Sign (ITS) - Series 1100  Revised conduit call-outs  Revised 30A-2P NEMA 4X DISC MTD ON SUPPORT DETAIL. Removed pad mounted transformer.
Sheet 7 Sheet 7 Sheet 8  M-ITS-1000  M-ITS-1001  M-ITS-1100  M-ITS-1100  M-ITS-1100	Removed Protective Coat quantity since not required to be applied to shoulder foundation.  Added note 5 to clarify limits of protective coat and revised protective coat quantity in Median Foundation Schedule.  Pole Assembly-Series 1000  ELEVATION VIEWS POLE MOUNTED ITS ELEMENT ASSEMBLY  Added 30A-2P NEMA 4X DISC MTD ON SUPPORT DETAIL.  GENERAL NOTES POLE MOUNTED ITS ELEMENT ASSEMBLY  Added Note 16 regarding disconnect switch usage.  ITS STANDARD FOUNDATION: New Sheet  Dynamic Message Sign (ITS) - Series 1100  Revised conduit call-outs  Revised 30A-2P NEMA 4X DISC MTD ON SUPPORT DETAIL. Removed pad mounted transformer.  Revised 30A-2P NEMA 4X DISC MTD ON SUPPORT DETAIL. Revised Note 2 to eliminate 120/208V and pad mount.
Sheet 7 Sheet 7 Sheet 8  M-ITS-1000  M-ITS-1001  M-ITS-1100  M-ITS-1100  M-ITS-1100  M-ITS-1100	Removed Protective Coat quantity since not required to be applied to shoulder foundation.  Added note 5 to clarify limits of protective coat and revised protective coat quantity in Median Foundation Schedule.  Pole Assembly-Series 1000  ELEVATION VIEWS POLE MOUNTED ITS ELEMENT ASSEMBLY  Added 30A-2P NEMA 4X DISC MTD ON SUPPORT DETAIL.  GENERAL NOTES POLE MOUNTED ITS ELEMENT ASSEMBLY  Added Note 16 regarding disconnect switch usage.  ITS STANDARD FOUNDATION: New Sheet  Dynamic Message Sign (ITS) - Series 1100  Revised conduit call-outs  Revised 30A-2P NEMA 4X DISC MTD ON SUPPORT DETAIL. Removed pad mounted transformer.  Revised 30A-2P NEMA 4X DISC MTD ON SUPPORT DETAIL. Revised Note 2 to eliminate 120/208V and pad mount.  Cabinet Wiring-Series 1200
Sheet 7 Sheet 7 Sheet 8  M-ITS-1000  M-ITS-1001  M-ITS-1100  M-ITS-1100  M-ITS-1100  M-ITS-1100	Removed Protective Coat quantity since not required to be applied to shoulder foundation.  Added note 5 to clarify limits of protective coat and revised protective coat quantity in Median Foundation Schedule.  Pole Assembly-Series 1000  ELEVATION VIEWS POLE MOUNTED ITS ELEMENT ASSEMBLY  Added 30A-2P NEMA 4X DISC MTD ON SUPPORT DETAIL.  GENERAL NOTES POLE MOUNTED ITS ELEMENT ASSEMBLY  Added Note 16 regarding disconnect switch usage.  ITS STANDARD FOUNDATION: New Sheet  Dynamic Message Sign (ITS) - Series 1100  Revised conduit call-outs  Revised 30A-2P NEMA 4X DISC MTD ON SUPPORT DETAIL. Removed pad mounted transformer.  Revised 30A-2P NEMA 4X DISC MTD ON SUPPORT DETAIL. Revised Note 2 to eliminate 120/208V and pad mount.  Cabinet Wiring-Series 1200  Cabinet Wiring
Sheet 7 Sheet 7 Sheet 8  M-ITS-1000  M-ITS-1001  M-ITS-1100  M-ITS-1100  M-ITS-1104  M-ITS-1200  All	Removed Protective Coat quantity since not required to be applied to shoulder foundation.  Added note 5 to clarify limits of protective coat and revised protective coat quantity in Median Foundation Schedule.  Pole Assembly-Series 1000  ELEVATION VIEWS POLE MOUNTED ITS ELEMENT ASSEMBLY  Added 30A-2P NEMA 4X DISC MTD ON SUPPORT DETAIL.  GENERAL NOTES POLE MOUNTED ITS ELEMENT ASSEMBLY  Added Note 16 regarding disconnect switch usage.  ITS STANDARD FOUNDATION: New Sheet  Dynamic Message Sign (ITS) - Series 1100  Revised conduit call-outs  Revised 30A-2P NEMA 4X DISC MTD ON SUPPORT DETAIL. Removed pad mounted transformer.  Revised 30A-2P NEMA 4X DISC MTD ON SUPPORT DETAIL. Revised Note 2 to eliminate 120/208V and pad mount.  Cabinet Wiring-Series 1200


	Page Shoot	Drowings
	Base Sheet Drawing	Modification Summary Effective: 03-31-2016
Tollway Bas	se Sheet Rev	
		Weigh-In-Motion - Series 1600
Section M		WEIGH-IN-MOTION CABINET AND FOUNDATION DETAILS
		WEIGH-IN-MOTION IP CAMERA DETAILS WEIGH-IN-MOTION LOOP DETECTOR DETAILS
		WEIGH-IN-MOTION LOOP DETECTOR DETAILS WEIGH-IN-MOTION DETECTOR LOOP AND QUARTZ SENSOR DETAIL
		INSTALLATION DETAIL DETECTOR HOUSING & DETECTOR HOUSING ADAPTER
		WEIGH-IN-MOTION DETECTOR HOUSING DETAIL
		Flashing Sign Beacon - Series 1700
		FLASHING SIGN BEACON INSTALLATION BREAKAWAY ELECTRICAL DETAIL
	M-115-1701	FLASHING SIGN BEACON INSTALLATION WIRING DIAGRAM
		Conduit Details at Integral Abutment-Series 1900
	M-ITS-1900	CONDUIT DETAILS AT INTEGRAL ABUTMENT BRIDGE STANDARD SLOPE WALL
		Postinos Costano (PHO), Costino 0500
	M-BUS-2500	Business Systems (BUS)- Series 2500  CABLE CONDUIT SCHEDULE AND GENERAL NOTES
		LEGEND SYMBOL LIST, ABBREVIATIONS AND EQUIPMENT SCHEDULES
	M-BUS-2502	SINGLE LINE DIAGRAM AND UTILITY POWER CABLE/CONDUIT SCHEDULE
		CONTROL BUILDING LIGHTING PLAN AND MISCELLANEOUS DETAILS - MAIN PLAZA
		CONTROL BUILDING LIGHTING PLAN AND MISCELLANEOUS DETAILS - REMOTE PLAZA CONTROL BUILDING GROUNDING DETAILS - MAIN PLAZA
		CONTROL BUILDING GROUNDING DETAILS - MAINT LAZA  CONTROL BUILDING GROUNDING DETAILS - REMOTE PLAZA
		GROUNDING SCHEMATIC
		CONTROL BUILDING MISCELLANEOUS DETAILS
		UPS SINGLE LINE AND WIRING DIAGRAM MISCELLANEOUS SCHEMATIC DIAGRAMS
		VIDEO POWER JUNCTION BOX DETAIL - MAIN PLAZA
		VIDEO POWER JUNCTION BOX DETAIL - REMOTE PLAZA
		VIDEO WATCHDOG CAMERA DETAILS
		RAMP PLAZA MONOTUBE DETAILS ACM AND IPO LANES  LOOP JUNCTION BOX DETAIL
		CONTROL BUILDING LIGHTING AND RECEPTACLE PLAN - MAIN PLAZA
		CONTROL BUILDING LIGHTING AND RECEPTACLE PLAN -REMOTE PLAZA
		MISCELLANEOUS CROSS SECTION DETAILS COMED TRANSFORMER PAD DETAIL
		ELECTRICAL SITE PLAN - ACM AND IPO LANES
		UNDERGROUND ELECTRICAL PLAN - ACM AND IPO LANES - MAIN PLAZA
		PLAZA I-PASS PLANS - ACM AND IPO LANES
		UNDERGROUND ELECTRICAL PLAN - ACM AND IPO LANES - REMOTE PLAZA AUTOMATIC LANE ISLAND PLAN AND DETAILS 12 FOOT WIDE LANE
		IPASS ONLY (IPO) LANE ISLAND PLAN AND DETAILS 12 FOOT WIDE LANE
		TOLL EQUIPMENT WIRING DIAGRAM - ACM AND IPO LANES
		LOOP AND TREADLE INSTALLATION DETAILS - ACM AND IPO LANES
		CONTROL BUILDING TSIC - ACM AND IPO LANES - MAIN PLAZA CONTROL BUILDING TSIC - ACM AND IPO LANES - REMOTE PLAZA
		TSIC TERMINAL BLOCK LAYOUT - ACM AND IPO LANES
	M-BUS-2531	CONTROL BUILDING EQUIPMENT LAYOUT - ACM AND IPO LANES - MAIN PLAZA
		CONTROL BUILDING EQUIPMENT LAYOUT - ACM AND IPO LANES - REMOTE PLAZA
		CONTROL BUILDING R3 RACK - MAIN PLAZA CONTROL BUILDING R3 RACK - REMOTE PLAZA
		MISCELLANEOUS DETAILS -ACM AND IPO LANES
		PANELBOARD SCHEDULES FOR TP1 AND TP2 - ACM AND IPO LANES
		PANELBOARD SCHEDULES FOR MDP AND UPS UNITS - ACM AND IPO LANES
		FIBER INTERCONNECTIONS BETWEEN MAIN AND REMOTE PLAZAS - ACM AND IPO LANES PLAZA LANE CONTROL SIGNAL - ACM AND IPO LANES
		TRAFFIC LIGHT DETAILS - ACM LANES
		TRAFFIC LIGHT DETAILS - IPO LANES
		ELECTRICAL SITE PLAN AET LANES UNDERGROUND CONDUIT PLAN - MAIN PLAZA
		UNDERGROUND CONDUIT PLAN - MAIN PLAZA  UNDERGROUND CONDUIT PLAN - MAIN PLAZA PLAN - REMOTE PLAZA
	M-BUS-2545	CONTROL BUILDING EQUIPMENT LAYOUT - REMOTE PLAZA
		CONTROL BUILDING EQUIPMENT LAYOUT - MAIN PLAZA
		CONTROL BUILDING TSIC - MAIN AND REMOTE PLAZAS - AET LANES TSIC TERMINAL BLOCK LAYOUT - ACM AND IPO LANES REMOTE PLAZAS - AET LANES
		PANELBOARD SCHEDULES - MAIN PLAZA AET LANES
	M-BUS-2550	PANELBOARD SCHEDULES - REMOTE PLAZA AET LANES
		WIRING DIAGRAM - AET 3 LANE LAYOUT
		WIRING DIAGRAM - AET 3-LANE LAYOUT  LOOP PLAN - AET 1-LANE LAYOUT
		LOOP PLAN - AET 1-LANE LATOUT  LOOP PLAN - AET 3-LANE LAYOUT
		VES WASH SYSTEM ENCLOSURE DETAIL
		VES WASH SYSTEM FLOW DIAGRAM AND MECHANICAL DETAIL
		VES WASH SYSTEM FLOW DIAGRAM AND MECHANICAL DETAIL VES WASH SYSTEM SUGGESTED CONDUIT ROUTING
	M-BUS-2559	VES WASH SYSTEM MISCELLANEOUS POWER WIRING DIAGRAM
	M-BUS-2560	VES WASH SYSTEM CONTROL SWITCH SCHEMATIC



- 2. CONCRETE = 4,000 PSI (MIN.)
  3. REBAR=EPOXY COATED FY=60,000 PSI (MIN.)
  4. PROVIDE SHOP DRAWINGS PRIOR TO CONSTRUCTION
- 5. INCLUDE CONDUITS

WIM CONTROLLER FOUNDATION DETAILS

SCALE: NTS



### NOTES:

- 1. THE WIM INTERNAL CABINET LAYOUT SHALL BE AS PER WIM MANUFACTURER'S RECOMMENDATION AND APPROVED BY THE ILLINOIS TOLLWAY.
- 2. SEAL CABINET TO FOUNDATION JOINT WITH SILICONE SEALANT TO PREVENT WATER INTRUSION. LOCATE CABINET ABOVE HIGH WATER LEVEL.
- 3. INSTALL 2" PVC SPARE CONDUIT FOR FUTURE USE. EXTEND 12" OUTSIDE OF CONCRETE FOUNDATION. PROVIDE CONDUIT MARKING FOR EASE OF FUTURE LOCATING.

NOTE TO DESIGNER

THIS BASE SHEET SHOWS TYPICAL NEW CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.

M-ITS-1600



WEIGH-IN-MOTION CABINET AND FOUNDATION DETAILS

3-31-2016

# NOTE TO DESIGNER THIS BASE SHEET SHOWS TYPICAL NEW CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET. NOTE: -SIDE VIEW FIXED IP CAMERA (MOUNTED PARALLEL TO BARRIER WALL TO PREVENT DAMAGE FROM 1. CONTRACTOR TO SUPPLY 3/4" STAINLESS STEEL BANDING FOR ATTACHING EQUIPMENT. SEE NOTE 1 POLE MOUNT BRACKET-PER MANUFACTURER RECOMMENDATIONS -SURGE ARRESTOR ---POLE TOP CAP MEDIAN MOUNTED 50' ALUMINUM — LIGHT POLE (BY OTHERS) -HOOK ASSEMBLY WITH GRIP HOIST ATTACHED TO HOOK SIDE VIEW FIXED IP CAMERA-SEE NOTE 1 POLE MOUNT BRACKET PER MANUFACTURER RECOMMENDATIONS -CAT6A ETHERNET CABLE SURGE ARRESTOR--HANDHOLE 22.5' GALVANIZED STEEL POLE 8"x4" SHAFT TAPER, 10 GUAGE (0.1345 IN) WALL, 15" BOLT CIRCLE, NON-BOLTED FACTORY ASSEMBLED COMPLETE WITH CATGA ETHERNET-CABLE INTERNAL VIBRATION DAMPER (JT830048) - MEDIAN BARRIER WALL -HANDHOLE LANES SHOULDER -STAINLESS STEEL WIRE CLOTH -METAL HELIX FOUNDATION WITH 15" BOLT CIRCLE (JT836018) PER ILLINOIS TOLLWAY STANDARD DRAWINGS TO WIM CONTROLLER CABINET M-ITS-1601 2" CNC CONDUIT (SCH. 80) 2" CNC CONDUIT TO WIM CONTROLLER CABINET *Illinois* Tollway WEIGH-IN-MOTION IP CAMERA DETAILS DATE 3-31-2016

## PRE-FORMED LOOP DETECTOR SPLICE DETAIL


1" (25 mm) MIN TYP

- ① WESTERN UNION SPLICE SOLDERED WITH ROSIN CORE FLUX. ALL EXPOSED SURFACES OF THE SOLDER SHALL BE SMOOTH. THE WESTERN UNION SPLICES SHALL BE STAGGERED.
- 2 WCSMW 30/100 HEAT SHRINK TUBE, MINIMUM LENGTH 3" (75 mm), UNDERWATER GRADE.
- (3) WCSMW 30/100 HEAT SHRINK TUBE, MINIMUM LENGTH 6" (150 mm), UNDERWATER GRADE.


36" TO 60" (900 mm TO 1500 mm)

4 NO. 14 2/C TWISTED, SHIELDED CABLE.

- 5 LOOP CONDUCTOR WITH FLEXIBLE PLASTIC TUBE.
- 6 PRE-FORMED LOOP.
- TL POLYOLEFIN 2 CONDUCTOR BREAKOUT SEALS. TYCO CBR-2 OR APPROVED EQUAL.



# DETECTOR LOOP WIRING SCHEMATIC



A.LANE 1 IS THE LANE CLOSEST TO THE CENTERLINE OF THE ROADWAY.

B.LOOP #1 IS THE LOOP IN THE LANE DOWN STREAM OF THE BENDING PLATE SENSORS.

C. LABEL LOOP CABLE "IN" OR LOOP CABLE "OUT".

D.LABEL LOOP CABLE CLOCKWISE OR LOOP CABLE COUNTERCLOCKWISE.

### LOOP LEAD-IN CABLE TAG

### NOTES:

- 1. PREFORMED DETECTOR LOOPS SHALL BE USED, AS SHOWN ON THE PLANS, SINCE NEW CONCRETE PAVEMENT IS PROPOSED. INSTALLATION SHALL BE ACCORDING TO THE STANDARD SPECIFICATIONS AND MANUFACTURER RECOMMENDATIONS.
- 2.FOLLOW LOOP DETECTOR MANUFACTURER RECOMMENDATIONS FOR MINIMUM SEPARATION DISTANCE FROM REBAR MATS. USE STAND OFFS AS REQUIRED.

NOTE TO DESIGNER

THIS BASE SHEET SHOWS TYPICAL NEW CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING, IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT.


MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.

M-ITS-1602



WEIGH-IN-MOTION LOOP DETECTOR DETAILS

DATE 3-31-2016



### GENERAL NOTES:

- 1. SIGNAL AND POWER CABLES CAN NOT SHARE THE SAME PULL BOXES OR CONDUITS.
- 2. ALL LOOP LEAD-IN SPLICES MUST BE MADE IN PULL BOXES OR HAND HOLES.
- ALL CONNECTIONS BETWEEN LOOP AND LEAD CABLES ARE DONE IN PULL BOX AND ARE SOLDERED THEN SEALED FOR WATERPROOFING. NUMBER AND PLACEMENT OF PULL BOXES NOT SHOWN.
- 4. ROAD SURFACE PAVEMENT CONDITIONS MUST MEET CURRENT ASTM E1318 REQUIREMENTS TO ACHIEVE OPTIMAL SYSTEM PERFORMANCE.
- 5. CABLES MUST BE PROTECTED BY PVC SLEEVES WHERE THEY CROSS PAVEMENT JOINTS/CRACKS.

NOTE TO DESIGNER


THIS BASE SHEET SHOWS TYPICAL NEW CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT.
MICROSTATION FILES AND THE "CADD STANDARDS MANUAL"
ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.


M-ITS-1603



WEIGH-IN-MOTION DETECTOR LOOP AND QUARTZ SENSOR DETAIL DATE

3-31-2016





# DETECTOR HOUSING ADAPTER DETAIL

NOTE TO DESIGNER

THIS BASE SHEET SHOWS TYPICAL NEW CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT.


MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.

M-ITS-1604



CROSS SECTION OF HOUSING ADAPTER

INSTALLATION DETAIL DETECTOR HOUSING & DETECTOR HOUSING ADAPTER DATE



NOTE TO DESIGNER

THIS BASE SHEET SHOWS TYPICAL NEW CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT.

MICROSTATION FILES AND THE "CADD STANDARDS MANUAL"

ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.

M-ITS-1605



WEIGH-IN-MOTION DETECTOR HOUSING DETAIL

<u>3-31-20</u>16